

DRAWN BY : XXX

DATE : X/X/XX

JOB NO : XXXXX

SHEET X OF X

PROJECT : XXXXXXXX

38 ALUM ANGLE FRAME LEVEL BED

SCALE: N.T.S.

MODEL : KD38 SS GRATING W/ HIDDEN LOCKING DEVICES, ALUMINUM ANGLE FRAME - LEVEL BED APPLICATION. FRAMES ARE NOT WELDED.

# KADEE INDUSTRIES, INC.

7160 KRICK ROAD WALTON HILLS, OHIO 44146  
(800) 321-3827 TEL (440) 439-8650 FAX (440) 439-6889

### GENERAL SPECIFICATIONS : KD38

TREAD MATERIAL : TYPE 304 SS 0.090" x 0.138"  
#4 SATIN FINISH SPACE 0.125" ; SPACING +/- 0.005"

SUPPORT RODS : 0.281"DIA. SPACED 2" O.C.

CONSTRUCTION : EACH JUNCTURE OF SURFACE WIRES TO SUPPORT RODS SHALL HAVE ELECTRIC RESISTANCE WELDED JOINTS.

### OVERALL DIMENSION TOLERANCES :

GRATING : + 0", - 0.125", FRAME : + 0", - 0.125"

### MANUFACTURING TOLERANCES :



ANSI/NAAMM A202.1-MBG 531 APPLICABLE TO :  
ON CENTER MEASUREMENT OF TREAD MATERIAL  
DIAGONAL MEASUREMENTS (SQUARE)  
TRANSVERSE BOW (BEFORE FASTENING)  
LONGITUDINAL BOW (BEFORE FASTENING)

### MATERIAL TOLERANCES :


ASTM A484/A484M APPLICABLE TO SS ANGLES  
ASTM B221 APPLICABLE TO ALUM SHAPES

### SPECIAL NOTES :


\*GC/INSTALLER IS RESPONSIBLE FOR COPLANAR INSTALLATION OF MAT SURFACE TO SURROUNDING FLOOR CONDITIONS  
\*GIVEN THAT THE NUMBER OF SURFACE WIRES (TREAD MATERIAL) IN ONE FOOT IS ABOUT SIXTY, IT IS PROBABLE THAT ADJACENT PANELS' WIRES WILL NOT ALIGN IN EVERY CASE. IN MOST CASES, THE WIRES WILL ALIGN FOR SEVERAL INCHES THEN APPEAR TO WALK. THIS IS UNAVOIDABLE MANIFESTATION OF THE MANUFACTURING PROCESS. THIS CONDITION APPLIES TO THE SUPPORT RODS AS WELL. SIMILARLY IN MITERED CORNERS, THE VARIANCES OF SLOTS WITHIN THE NORMAL TOLERANCE RANGES PRECLUDES GUARANTEED ADJACENT PANEL WIRE ALIGNMENT.



PRODUCT MAY NOT COME TO A COMPLETE POINT WELD IN FILLER (AS NEEDED)



DETAIL X



SUPPORT RODS MAY NOT ALIGN

DETAIL A

NOTE : KD38 IS DESIGNED TO REST DIRECTLY ON THE RECESS FLOOR. (IT DOES NOT SPAN)

NOTE : DO NOT SCALE DRAWING.

38 3/8/17