

DRAWN BY:

DATE:

JOB NO:

SHEET OF

PROJECT:

KADEE
INDUSTRIES, INC.

71 60 KRICK ROAD □ WALTON HILLS, OHIO 44146
(800) 321-3827 □ TEL (440) 439-8650 □ FAX (440) 439-6889

GENERAL SPECIFICATIONS: Entec-38

TREAD MATERIAL: TYPE 304 SS WIRE #4 SATIN FINISH
SUPPORT RODS: 0.281" dia. SPACED 2" O.C.

SLOT OPENINGS: 0.130"
CONSTRUCTION: EACH JUNCTURE OF SURFACE WIRES
TO SUPPORT RODS SHALL HAVE WELDED JOINTS

OVERALL DIMENSION TOLERANCES:
GRATING: +0, -.125" , FRAME: +0, -.125"

MANUFACTURING TOLERANCES:
ANSI/NAAMM A202.1-MBG 531

MATERIAL TOLERANCES:
ASTM A484/A484M APPLICABLE TO SS ANGLES
ASTM B221 APPLICABLE TO ALUM SHAPES





SPECIAL NOTES:
*GC/INSTALLER IS RESPONSIBLE FOR COPLANAR
INSTALLATION OF MAT SURFACE TO SURROUNDING
FLOOR CONDITIONS.

INSERT TRACK: TYPE 304 SS 1-3/8" CHANNEL
SPACED 4" O.C.

CARPET: INSERTED TREADS ARE MADE OF 100% NYLON
FIBER OR 100% POLYPROPYLENE, FUSION
BONDED TO THE BACKING.

Frame Finish: MILL

Carpet Color:



HIDDEN LOCKDOWNS ARE LOCATED AT STARS (*'S) ON GRATING. USE ALL LOCKDOWNS PROVIDED.
SEAMS IN GRATING MAY NOT ALIGN WITH SEAMS IN FRAMING IN ALL CASES.

NOTE: ENTEC-38 IS DESIGNED TO REST DIRECTLY ON THE RECESS FLOOR. (IT DOES NOT SPAN)

DETAIL A: SUPPORT RODS MAY NOT ALIGN